

**Date: February 17, 2017**

**ROCKINGHAM COUNTY PUBLIC SCHOOLS**  
**PLEASANT VALLEY ELEMENTARY SCHOOL – RENOVATION AND ADDITION**  
**I.F.B. 082-95-00-101**  
**DAYTON LEARNING CENTER**  
**I.F.B. 082-95-01-100**  
**JOHN WAYLAND ELEMENTARY SCHOOL – RENOVATION AND ADDITION**  
**I.F.B. 082-97-00-101**

**ADDENDUM #2**

**GENERAL:**

Please inform all concerned that the Contract Documents are modified by this Addendum.

Acknowledge receipt of this Addendum by inserting addendum number and date in space provided on the Bid Form.

The following revisions, additions, and clarifications are hereby a part of the Contract Documents and supersede or otherwise modify the provisions of the published Project Manual and Drawings dated February 01, 2017.

**A. PROJECT MANUAL:**

**1. Section 09 29 00, Gypsum Board**

Page 3: **Add** "F" to part 2.2 as follows:

- F. High-Impact Type: Manufactured with Type X core, plastic film laminated to back side for greater resistance to through-penetration (impact resistant).
  - 1. Core: 5/8 inch thick.
  - 2. Plastic-Film Thickness: 0.020 inch.

**2. Section 23 09 00, Instrumentation and Control for HVAC**

Page 3: **Revise** paragraph 1.6 A, subparagraphs 1 through 5 to read as follows:

- 1. Air Handlers – one (1) controller
- 2. VAV Controllers – two (2)
- 3. Fan Powered VAV Controllers – two (2)
- 4. Damper Actuators – one (1) of each size/type
- 5. Valve Actuators – one (1) of each type

**END OF ADDENDUM #2**