



COMMONWEALTH of VIRGINIA

DEPARTMENT OF TRANSPORTATION
1401 EAST BROAD STREET
RICHMOND, VIRGINIA 23219 2000

Charles A. Kilpatrick, P.E.
Commissioner

April 28, 2017

ADDENDUM NUMBER FIVE

TO ALL PLANHOLDERS: **VDOT Charlottesville Old Residency: Interior Renovation & Roof Replacement**

Contractual Work – IFB 153857-TW

Project Code – 501-A6501-009

Bid Receipt Date: 2:00 P.M. (ET) May 10, 2017

Bid Opening Date: 2:00 P.M. (ET) May 11, 2017

Ladies and Gentlemen:

This Addendum Number Five shall be added to and shall become a part of the original bid documents.

The bid closing and opening dates have been changed as shown above.

- **Addendum Number Five sealed April 28, 2017, by William L. Allen (2 pages) including Pre-Bid questions and answers.**

Acknowledgement of receiving this addendum must be shown on the bid form in the space provided or your bid may be rejected.

Sincerely,

A handwritten signature in blue ink that reads 'B. Williams for Tamerra Webb'.

Tamerra D. Webb, VCCO
Contract Officer



1115 Vista Park Drive
Forest, Virginia 24551
(434) 316-6001 • (434) 316-6002 Fax


ADDENDUM NO. 5 INPUT

(2 pages – no attachments)

PROJECT INFORMATION

Owner: Virginia Dept. of Transportation	Owner's Project Mgr.: Leland Chen
Project Title: Old Charlottesville Residency Interior Renovation and Roof Replacement	Owner's Project Code: 501-A6501-009
	A/E Project Mgr.: Bill Allen, PE
	A/E Project No.: 14150
Project Location: Culpeper District	Bids Due: Refer to VDOT Addendum Cover Letter
IFB No.: 153857-TW	Bids Opened:

The following constitutes Addendum No. 5 for the referenced project. Bidders must acknowledge receipt of all addenda as required on the bid form.



1. RESPONSE TO PRE-BID QUESTIONS

- a. Question: Specification Section 096513, Page 2, Paragraph 2.1: Please confirm that Flexco Base Sculptures 6H + 3/8 gauge Profile Marquis is acceptable to bid. This is the only base that meets all specs. Corners to be mitre cut on site.
- Response: Yes, that product is acceptable to bid.
- b. Question: Drawing A1: Calls for ceramic base. Drawings and specs call for wall tile to floor. Specify a base if required.
- Response: Provide ceramic cove base in same size as wall tile.
- c. Question: Drawing A1: Finish Schedule calls for floor to be ceramic. No product specified.
- Response: Refer to changes to Specification Section 093013 listed below for floor tile.
- d. Question: Specification Section 093013, Page 1, Paragraph 1.2: No floor tile specified – please provide specs.
- Response: Refer to changes to Specification Section 093013 listed below for floor tile.
- e. Question: Specification Section 093013, Page 1, Paragraph 2.3: Ceramic installers to provide mudset and epoxy grout? Correct?
- Response: For wall tile, use Modified Dry Set Mortar, ANSI A118.4 and Epoxy Grout, ANSI A118.3.

2. CHANGES TO DRAWINGS AND SPECIFICATIONS

- a. Specification Section 093013, Ceramic Tiling: Add the following to Section 2.3:

B. Ceramic Tile: Porcelain Floor Tile.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
 - a. American Marazzi Tile, Inc.
 - b. American Olean; a division of Dal-Tile Corporation.
 - c. Crossville, Inc.
 - d. Daltile.
 - e. Interceramic.
2. Composition: Impervious.
3. Module Size: 12 by 12 inches.
4. Thickness: 3/8" nominal.
5. Surface: Slip resistant.
6. Dynamic Coefficient of Friction: Not less than DCOF AcuTest 0.42.
7. Finish: Unpolished.
8. Tile Color and Pattern: To be selected by A/E from manufacturer's full range of standard colors. Pattern to be selected during construction.
9. Grout Color: To be selected by A/E from manufacturer's full range of standard colors.
10. Trim Units: Coordinated with sizes and coursing of adjoining flat tile where applicable. Provide shapes as follows, selected from manufacturer's standard shapes:
 - a. Base for Portland Cement Mortar Installations: Cove.

b. Specification Section 093013, Ceramic Tiling: Add the following to Section 3.2:

C. Fill cracks, holes, and depressions in concrete substrates for tile floors installed with thinset mortar with trowelable leveling and patching compound specifically recommended by tile-setting material manufacturer.

c. Specification Section 093013, Ceramic Tiling: Add the following to Section 3.3.F:

1. Porcelain Tile: 1/8 inch.

d. Specification Section 093013, Ceramic Tiling: Add the following to Section 3.7:

B. Interior Floor Installations, Concrete Subfloor:

1. Ceramic Tile Installation TCNA F115-15: Thin-set mortar on crack isolation membrane; TCNA F125-Partial-15.

END OF ADDENDUM INPUT